



Accelerator R&D at ALBA

Francis Perez





- ALBA
 - Accelerators
 - Beamlines
 - Operation
- R&D on Accelerators
 - FCC – CERN
 - CLIC – CERN
 - ELI-NP – INFN
 - RF lab
 - Magnetic lab
 - Vacuum lab






ALBA Synchrotron Light Source

- ✓ 3 GeV electron accelerator
- ✓ 7 running beam lines + 1 in commissioning + 2 in construction
- ✓ Funding is 50% Spanish – 50% Catalan Governments
- ✓ First beam for users May 2012





ALBA Accelerators





ALBA Synchrotron Light Source

Approved in 2003

First users in 2012



June 2006






2007





2008





2009









2011





Linac

Accelerate electrons from rest to 100 MeV
RF cavities 3 GHz
Repetition rate of 3 Hz



Booster




Accelerate e- from 100 MeV to 3 GeV
1 x RF cavity at 500 MHz
Repetition rate of 3 Hz



Storage Ring

Keep electrons at 3.0 GeV
Magnets and correctors to keep the orbit (sub- μm)
Vacuum Pumps (10^{-10} mbar)
6 x RF cavities at 500 MHz
Circulating current: 250 mA

16th March 2011



you are here: [home](#) → [news & events](#) → [all news](#) → [the first users have started their experiments at alba](#)

navigation

- All events
- All news
- The first users have started their experiments at ALBA**

The first users have started their experiments at ALBA

Created by [Anne-Cécile KLORA](#) — last modified May 17, 2012 12:52 PM

BOREAS is the first of ALBA 7 beamlines to be available to users.

The standard proposal 'Ferrite magnetic nanoparticles and hybrid superconducting layers: a XMCD spectroscopic study', granted with 18 shifts, started running experiments at ALBA on May 7th, 2012.

The aim of the experiment is to clarify and characterize the atomic origin of the magnetism in different ferrite nanoparticles, both in assynthesized form as well as embedded in high temperature superconductor (HTS) thin films.




Alba would like to thank all participants in this call for proposals for their interest in our Facility and the high level of scientific proposals, as acknowledged by the Scientific Panel.




ALBA acting Director, the User Office team, the BOREAS beamline team and the first external users from Unidad de Química Inorgánica- Departamento de Química- UAB, Barcelona.


Scientific areas in ALBA

**LIFE
SCIENCE**




**CONDENSED
MATTER**

CHEMISTRY



photon energy:
from UV up to hard
X-ray of tens of keV



ALBA BEAMLINES





ALBA BEAMLINES




Some pictures





ALBA BEAMLINES

Some pictures





Operation 2016

ALBA Operations Calendar 2016

BL operation	BL BL users and commissioning
M operation	M Start up and optimization of accelerators with beam
Shutdown Warm	W No beam. Services ON.
Shutdown OFF	Off No beam. No cooling water.
Public & CELLS holiday	

Weekday	January				February				March				April				May				June				July				August				September				October				November				December				
	Day	Week	M	A	N	Day	Week	M	A	N	Day	Week	M	A	N	Day	Week	M	A	N	Day	Week	M	A	N	Day	Week	M	A	N	Day	Week	M	A	N	Day	Week	M	A	N									
Mo																																																	
Tu																																																	
We																																																	
Th																																																	
Fr																																																	
Sa																																																	
Su																																																	

Scheduled Accelerator Operation [h]

5744

Scheduled User Beam [h]

4368


Operation

24/24h - 7/7d



Operation 2016



High Brightness Beams... Jobs -- CELLS www.cells.es/static/Files... CELLS - ALBA Synchrotr... XLIV International Meeti... 2016 (11-15 April 2016) 2015 (23-29 March 2015)

Current	128.393 mA	MIRAS	FI03 Closed	M1 -260.00 mm
Life Time	21h 24m (2765.9)	MSPD	FE04 Open	SCW30 B = 2.102 T
Pressure	4.23e-10 mbar	MISTRAL	FE09 Open	BEND
		NCD	FE11 Open	IVU21 5.87 mm
Friday 08-Apr-2016 09:52:18		XALOC	FE13 Open	IVU21 6.68 mm
Beam for BLs. Top-up.		CLAESS	FE22 Open	MPW80 12.90 mm
		CIRCE	FE24 Open	EU62 43.31 mm
		BOREAS	FE29 Open	EU71 39.91 mm



Operation

	2012	2013	2014	2015	2016
Total Scheduled [h]	3280	4464	5240	5728	5760
Accelerators [h]	892 27.2%	924 20.7%	1352 25.8%	1408 24.6%	1392 24.2%
Beam lines [h]	2388 72.8%	3540 79.3%	3888 74.2%	4320 75.4%	4368 75.8%
BL Availability	77.0%	83.8%	96.8%	97.3%	
MTBF [h]	21.0	25.0	33.7	51.4	
MTTR [h]	1.0	0.8	1.1	1.4	





The ALBA Team
We are today ~200



The ALBA Team Expertise

Inside ALBA Dampy Cavity

- Accelerator beam dynamics
- Accelerators operation
- RF systems and test laboratory
- Magnetic structures design and measurements laboratory
- Ultra High Vacuum systems design and test laboratory
- Beam diagnostics and test laboratory
- Real time control systems and data acquisition
- High power and high stability power supplies
- High precision mechanics
- High speed electronics, synchronisation and timing systems
- Survey, alignment and vibrational measurements

Magnets



Diagnostics



RF Cavities

Timing

Control System

Digital Electronics



Vacuum

International Collaborations

- FCC - Future Circular Collider

 - EU H2020 Project EuroCirCol

 - WP4: Cryogenic Beam Vacuum System




- Collaboration with CLIC-CERN:

 - WP1: Damping Ring Stripline Kicker test
 - WP2: Collective Effects
 - WP3: Beam Instrumentation & Diagnostics
 - WP4: 1.5 GHz RF System



- Collaboration with INFN for the ELI-NP project

 - WP1: Magnetic simulations
 - WP2: BPM measurements






FCC Project

Future Circular Collider

100 TeV pp collider



90 – 100 Km



Horizon 2020
H2020-INFRADEV-1-2014-1
RIA action, proposal number 654305

Four technical Work Packages: *One lead by ALBA-CELLS*

The Future Circular Collider study




EC Funded Scope

Lead: **CEA**
A. Chancé

Co-Lead: CERN
D. Schulte



Arc Design




EIR Design

Lead: **JAI**
A. Seryi


Co-Lead: CERN
D. Schulte

Lead: **CELLS**
F. Perez

Co-Lead: CERN
P. Chiggiato



Cryo Beam Vacuum






High Field Magnet

Lead: **CERN**
L. Bottura

Co-Lead: **TBA**
TBA


Design, Prototyping and Tests of the FCC-hh Vacuum Beam Screen

Prototyping ongoing





CLIC Project Compact Linear Collider





CLIC Collaboration



- **Contract KT with CERN**

for the contribution of ALBA to the CLIC study on 26th May 2015.

- **Four Work Packages:**

- **WP1: Damping Ring Stripline Kicker test (M.Barnes & M.Pont)**

The Stripline Kicker of the CLIC Damping Ring will be installed at ALBA for testing its performance in terms of stability

- **WP2: Collective Effects (G.Rumolo & U.Iriso)**

ALBA Storage Ring will be used for test bench of beam instabilities computations

- **WP3: Beam Instrumentation & Diagnostics (F.Rondarolo & U.Iriso)**







Development of new fast and high resolution instrumentation is being developed and tested at ALBA

- **WP4: 1.5 GHz RF System (H.Schmickler & F. Perez)**

The RF system for the CLIC Damping Ring will be designed by ALBA

WP1: DR Stripline Kicker test


Design vacuum chamber transitions



WP1: DR Stripline Kicker test

Design vacuum chamber transitions


FEA of the radiation absorber (Temp, stress, strain)



WP2: Transverse Impedance Measurements

- A transverse impedance source produces a small defocusing kick:




$$\Delta K \propto Q \times \text{Im}(Z)$$
- The bunch charge dependency of such defocusing kick provides the key to disentangle the small contribution produced by each impedance source from the dominating focusing effects due to the machine optics.





WP3: Instrumentation Interferometry Measurements

Bunch by bunch beam size measurements using Fast Gated Camera




WP4: Desing RF 1.5 GHz


Measurement of beam loading induced phase shift

ALBA FF Loop for beam loading compensation

- ✓ In Normal Operation: Effect of beam loading negligible
 - Revolution frequency $\sim 1\text{MHz}$
 - 90% Filling Pattern
 - 10 trains: 10 x (32 bunches + 12 empty buckets)
- ✓ Filling pattern modified to 1/3 to be able to measure beam loading effect





RF Trip Compensation for Beam Stability - ESLS-RF Oct 2015 - Max-IV




ALBA FF Loop for beam loading compensation

- ✓ Beam Loading measured with 1/3 filling pattern (60mA)



- Beam Phase modified by 5° due to beam loading effect
- Future upgrade: Phase modulation (feed-forward loop) to compensate this effect
- Needed to prove feasibility of this approach for CLIC collaboration

RF Trip Compensation for Beam Stability - ESLS-RF Oct 2015 - Max-IV



ALBA R&D labs


- Magnetic lab
- RF lab
- Vacuum lab

Magnetic Measurements Laboratory

- Specialized in **accurate** measurements of **big** magnetic structures

Mission of the laboratory:

1. Measurement of Accelerators Magnets
2. Construction and measurement of IDs





Fixed stretched wire bench

Hall probe bench


Flipping coil bench

Rotating coil bench

Helmholtz coils

Magnetic Measurements Laboratory


Collaboration with other research centers



Magnets built by industry



CIEMAT magnets for IFMIF



SESAME dipoles –
CERN agreement



CIEMAT phase
shifter for E-XFEL


Magnetic Measurements Laboratory

Collaborations/Contracts

- Magnetic Lab
 - SESAME Dipoles, done
 - IFMIF Quads, done
 - Elytt/LEHIPA permanent magnets quads, on going
 - CIEMAT cyclotron magnet (new magnetic bench, 2016)
 - ThomX magnets (2016)
 - ANTEC - CNAO
 - Other collaborations under discussion




- Specialized in **low** and **high RF power** measurements and **cavity conditioning**




In order to build the accelerators, ALBA did set up a complete **high power RF laboratory** for **prototype testing** and **cavity conditioning**:

1. LLRF tests
2. Controls tests
3. 80 kW amplifier IOTs tests
4. High power RF conditioning of:
 - Cavities
 - Input power couplers



High Power RF Laboratory



IOT cabinet

HVPS



RF transmitter



LLRF and Controls racks




Cavity inside the Bunker




High Power RF Laboratory

Collaboration with other research centers



CIEMAT
IFMIF Buncher cavity
at ALBA RF lab for High Power Conditioning
(2014 & 2015)



CIEMAT - Cyclotron Cavity (2016)

Vacuum Laboratory

- Specialized in **Ultra High Vacuum: design, construction and tests.**



Vacuum Laboratory

Installation and Material :

- Clean room class 100000 (ISO 8)
- Bake out oven (length 14m,height 1m,width 2m)
- 12 roughing station
- 7 leak detectors
- Material for bake out (controllers, heaters ...)
- Ion pumps
- Residual gas analyser
- Vacuum measurement gauges
- Traveling crane (1T)



Design and Calculation

- Nx (Siemens) Cad system
- Ansys for calculation
- Molflow for vacuum calculation




Vacuum Laboratory

Collaboration with other research centers

MAXLAB (Sweden):

- Design of vacuum chambers for the 3Gev and 1,5Gev MaxIV Storage Rings
- Thermal, mechanical and vacuum calculation
- Technical specifications & CFT process



Salamanca University (Spain)

- Design and calculation of a vacuum chamber for a 200TW laser compressor optical devices
- Technical specifications & CFT process
- Fabrication follow-up
- Installation and vacuum tests




EuroCirCol – H2020 for FCC (CERN)



Horizon 2020
H2020-INFRADEV-1-2014-1
RIA action, proposal number 654305

In conclusion



The construction of the ALBA accelerator complex has created at CELLS a large group of experts of scientists, engineers and technicians on the state of the art accelerator technologies.

Staff of ALBA, in 2016, is 200 persons with around 160 being technicians, engineers and scientists.